QUALITY ASSURANCE PLAN (SRCG IM PHASE) Drg . No. 064706A-00									Issue No : 01 Rev No: Date of Issue 10/06/ 2021
Material	As per Assembly P								
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by GM/OFT (Review/Witness)	Remarks
	General appearance	Non Critical	Visual	100%			Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
Body External Welded (Raw material)	Chemical properties	Non Critical	Chemical Lab analysis	100%	As p	er Assembly Part List.	Test report from NABL lab	R	
	Mechanical properties	Non Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - Turning, Milling,Drilling, Reaming, Threading, etc.,	Dimensions Specified in the Inspection report of the component	Non Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%	Approved Drg No. 064706A-00	As per Approved Drg No. 064706A-00	Firm Inspection report	W	
A dry film lubrication in a fluoropolymer organic resin Class-2, color matte black	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 064706A-00	TYPE I, 5-13 MICRON THICK PER VS-1-3-1-165 (OR EQUIVALENT).	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Welding	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 064706A-00	WELDING PER AWS D1.1 GTAW OR GMAW USING ELECTRODE ER80SD-2 PER AWS A5.28 OR ELECTRODE ER70S-2 PER AWS A5.18. VISUAL INSPECTION.	Firm Inspection report	W	
Final Inspection	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 064706A-00	As per Approved Drg No. 064706A-00	Firm Inspection report	W	

^{*} Note: 1. Clause indicated in the drawing to be followed 2. Process audit on Dry film lubrication, Welding and Traceability of Raw materials to Final Product (Man,Material,Machine and Methods)

	Issue No : 01 Rev No: Date of Issue 10 /06 / 2021								
rg . No. 064708A-00									
Nomenclature	POINTER : FOR BO	OFT/QAP/SRCG/064708A-00							
Material	ALLOY STEEL PLA								
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by GM/OFT (Review/Witness)	Remarks
POINTER (Raw material)	General appearance	Non Critical	Visual	100%		l	Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
	Chemical properties	Non Critical	Chemical Lab analysis	100%		ATE SAE 4130 NORMALIZED PER OR SAE 4340 NORMALIZED PER AMS-6359.	Test report from NABL lab	R	
	Mechanical properties	Non Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - As per approved drg.no. 064707A-00	Dimensions Specified in the Inspection report of the component	Non Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%	Approved Drg No. 064708A-00	As per Approved Drg No. 064708A-00	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Final Inspection	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 064708A-00	As per Approved Drg No. 064708A-00	Firm Inspection report	W	

Note: 1. Clause indicated in the drawing to be followed
 2. Process audit on Traceability of Raw materials to Final Product (Man,Material,Machine and Methods)

QUALITY ASSURANCE PLAN (SRCG IM PHASE)									Issue No : 01 Rev No: Date of Issue 10 /06/ 2021	
Drg . No. 064707A-00										
Nomenclature	BODY EXTERNAL									
Material	ALLOY STEEL BA	OFT/QAP/SRCG/064707A-00								
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by GM/OFT (Review/Witness)	Remarks	
Body External (Raw material)	General appearance	Non Critical	Visual	100%	MATERIAL: A	ALLOY STEEL BAR RND SAE 4130 NORMALIZED PER 58 OR SAE 4340 NORMALIZED PER SAE-AMS-S-5000.	Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency	
	Chemical properties	Non Critical	Chemical Lab analysis	100%	SAE-AMS-S-675		Test report from NABL lab	R		
	Mechanical properties	Non Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R		
In process - As per approved drg.no. 064707A-00	Dimensions Specified in the Inspection report of the component	Non Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%	Approved Drg No. 064707A-00	As per Approved Drg No. 064707A-00	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same submitted	
Final Inspection	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 064707A-00	As per Approved Drg No. 064707A-00	Firm Inspection report	W		

^{* &}lt;u>Note:</u> 1. Clause indicated in the drawing to be followed 2. Process audit on Traceability of Raw materials to Final Product (Man,Material,Machine and Methods)