QUALITY ASSURANCE PLAN (SRCG IM PHASE)									Issue No : 01 Rev No: Date of Issue 05 /06/ 2021
Drg . No.	069201A-00								
Nommenclature	ADAPTOR,SPRING								OFT/QAP/SRCG/069201A
Material	CRES BAR TYPE 17-4PH PER AMS 5643.								
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by QAE(N), Chennai or by Nominated Agency (Review/Witness)	Remarks
	General appearance	Critical	Visual	100%			Firm Inspection report	R	
Adaptor Spring (Raw material)	Chemical properties	Critical	Chemical Lab analysis	100%	CRES BAR TYPE 17- 4PH PER AMS 5643	CRES BAR TYPE 17-4PH PER AMS 5643	Test report from NABL lab		Sample will be drawn and sealed by Inspection Agency
	Mechanical properties	Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - Milling ,Drilling, Reaming	Dimensions Specified in the Inspection report of the component	Critical	Dimensional measurement		Approved Drg No. 069201A-00	As per Approved Drg No. 069201A-00	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Passivation treatment	General appearance	Critical	Visual and Dimensional Checks		111	PER AMS-2700 METHOD 1 TYPE 8.	Firm Inspection report	W	
Baking	General appearance	Critical	Visual and Dimensional Checks		Approved Drg No. 069201A-00	Bake part after plating within 3 hours as per AMS-2759/9 Table 1 for 3 hours minimum at 191°C.	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Final inspection	General appearance	Critical	Visual and Dimensional Checks			As per Approved Drg No.069201A-00	Firm Inspection report	w	
* Note Process audit on passivation treatment, Backing and Traceability of Raw materials to Final Product (Man,Material,Machine and Methods)									