

QUALITY ASSURANCE PLAN (SRCG IM PHASE)									Issue No : 01 Rev No:
									Date of Issue 05 / 06 / 2021
Drg . No.	Y28657A-00								OFT/QAP/SRCG/Y28657A
Nomenclature	SPRING FLAT								
Material	CRES PLATE THICK 0.3 MM AISI 302/304 1/4 OR 1/2 HARD PER ASTM-A-666.								
Component Nomenclature/ operations	Charateristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by QAE(N), Chennai or by Nominated Agency (Review/Witness)	Remarks
Spring Flat (Raw material)	General appearance	Non Critical	Visual	100%	CRES PLATE THICK 0.3 MM AISI 302/304 1/4 OR 1/2 HARD PER ASTM-A-666.	CRES PLATE THICK 0.3 MM AISI 302/304 1/4 OR 1/2 HARD PER ASTM-A-666.	Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
	Chemical properties	Non Critical	Chemical Lab analysis	100%			Test report from NABL lab	R	
	Mechanical properties	Non Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - Milling, Drilling, Reaming, Bending	Dimensions Specified in the Inspection report of the component	Non Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%	Approved Drg No. Y28657A-00	As per Approved Drg No. Y28657A-00	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Dry Film Lubrication in a FluoroPolymer Organic Resin Class 2 colour Matte Black Type 1	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. Y28657A-00	15-25 Micron Thick per VS-1-3-1-165 (or equivalent)	Firm Inspection report	W	
Final Inspection	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. Y28657A-00	As per Approved Drg No. Y28657A-00	Firm Inspection report	W	
* Note 1. Process audit on Dry Film Lubrication and Traceability of Raw materials to Final Product (Man,Material,Machine and Methods)									