QUALITY ASSURANCE PLAN (SRCG IM PHASE)									Issue No : 01 Rev No: Date of Issue 05/06 / 2021
Org . No. 074263A-00									03/00 / 2021
Nommenclature									OFT/QAP/SRCG/074263A
Material									
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms		Inspection by QAE(N), Chennai or by Nominated Agency (Review/Witness)	Remarks
Piston Inner (Raw material)	General appearance	Critical	Visual	100%	- CRES BAR TYPE 17- 4PH PER AMS -5643 PURCHASED IN CONDITION H1150	CRES BAR TYPE 17-	Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
	Chemical properties	Critical	Chemical Lab analysis	100%			Test report from NABL lab	R	
	Mechanical properties	Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - Turning, Milling, Drilling, Reaming , Threading	Dimensions Specified in the Inspection report of the component	Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%		As per Approved Drg No. 074263A-00	Firm Inspection report		Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Passivation treatment	General appearance	Critical	Visual and Dimensional Checks		Approved Drg No. 074263A-00	PER AMS-2700 METHOD 1 TYPE 8	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Baking	General appearance	Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 074263A-00	BAKE PART AFTER PLATING WITIN 3 HOURS PER AMS-2759/9 TABLE 1 FOR 3 HOURS MINIMUM AT 191 C.	Firm Inspection report		
Final inspection	General appearance	Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	11	As per Approved Drg No.074263A-00	Firm Inspection report	W	
Note 1. Clause 6 indicated in the drawing to be followed 2. Process audit on passivation treatment, Backing and Traceability of Raw materials to Final Product (Man, Material, Machine and Methods)									