



Scope of work for supply of Quick lime:

1. Delivery Schedule: Firm should make arrangement to supply the material in batch/lot wise to MSF, Ishapore as per user demand which will be intimated to the firm in advance.
2. Specification: The material should be as per MSF specification and firm should supply chemical test certificate from NABL certified laboratory along with the material for each lot.
3. Delivery: Firm should make arrangement for delivery and unloading of material at MSF on its own cost.
4. Packaging and Size: ^{lump} Material size should be 50 to 75 MM \pm 10 MM and should be packed in 40/50 Kg double polythene /plastic moisture free bags.
5. Special Clause: During Furnace relining and major breakdown no material should be supplied by the firm. Advance intimation shall be given to the firm in such situation.


JT.GM/F
10/9/16

on leave
AWM/SMR


HOS/SMR
10/9/16