PRE-QUALIFICATION CRITERIA FOR CYLINDER JACKET LH & RH (FULLY FINISHED) TO DRG No SB 303-03-16 & 303-02-23

- 1. The prospective vendors must be supplying or must have supplied large intricate aluminium engine casting to reputed engine manufactures.
- 2. The vendors, who are interested in supplying such castings, with fully machining should have their own manufacturing facilities or should have tie up for getting the castings from reputed manufacturers. The firm should have a large manufacturing base, adequate financial strength and well-documented quality system. The manufacturer should have adequate infrastructure like sufficient area of industrial shed, power backup, air compressors etc.
- 3. The casting manufacturer shall buy all input materials for liquid metal as well as for moulding and core making from reputed manufacturers only. Necessary material certificates for all input materials and additives should be available.
- 4. The vendors must have adequate trained, experienced and skilled manpower.

5. Cylinder Jacket Castings to drg.no. 303-06-24 SB:

THE FIRM/TIED UP FIRM SHOULD HAVE FOLLOWING FACILITIES:

- a) Aluminium melting furnace with adequate capacity.
- b) Suitable core making facilities (like hot box, cold box and shell core) with latest core shooter and related mixers, core ovens etc.
- c) Capacity for manufacturing Die Casting dies with simulation preferably.
- d) Heat treatment for T6 process wherever required (solutionising and ageing facilities.)
- e) Abrasive blasting / surface cleaning facilities.
- f) Fettling facilities like band saw, mechanical grinders etc.
- g) The Firm should have Degassing plant.
- h) Transfer Ladles, holding (preferably with dosing facility) furnaces.
- i) The firm should have density meter and porosity detection systems to check the effect of the degasification.
- j) Hydraulically operated gravity die casting machines.
- k) Vacuum Impregnation plant for sealing micro porosity.
- The general quality requirement of the casting to be manufactured by the vendor shall confirm to the technical document TTM 27-87.
- m) Pressure testing facilities.
- n) Argon TIG welding facility.

6. THE FIRMSHOULD HAVE THE FOLLOWING FACILITIES COMPULSORY AT THEIR PREMISES FOR FULLY FINISHED Cylinder Jacket to Drg. No SB 303-03-16 &SB 303-02-23

- a. HMC/VMC with axes strokes to accommodate component size 1200 x 300 x 250 mm (L x W x H) and weight 45 Kg.-
- b. Radial drilling machine.
- c. Firm should have expertise in designing of complex fixtures, special tools and gauges in house or tie up with for designing and manufacturing of complex fixtures, special tools.
- d. Firm should have sufficient space and facilities for deburring and checking the components.
- e. Firm should have skilled fitters to carried out the critical fitting operations.
- f. All embodiment/fitment items (i.e. studs, pins, end plug etc.) are to be procured from the reputed firms and to suit the technical requirement as per drawing and process schedule.

- g. Adequate material handling facilities like EOT cranes, forklifts etc.
- h. Component washing facility like jet washing facilities should be available / created.
- i. Firm should be capable to design and develop the fixture and other facilities required to carry out the pressure testing operation. Firm should have (or) create pressure testing facilities at their premises after receipt of the supply order .After completion of all machining operation the last operation pressure testing should be carried out. Final acceptance of the component / Assembly may be decided based on Water pressure testing outcome. Water temperature, pressure and duration of testing should be maintained as per drawing / process sheet.
- j. Firm shall be full responsibility for the quality of the component supplied to Engine factory till final engine performance clearance in the field.

QC CRITERIA

Testing facilities and test equipment's and lab (preferably NABL accredited) should include following facilities:

- i) Radiography / Ultrasonic testing equipment.
- ii) Sand lab for green sand and core sand testing and analysis.
- iii) Wet gravimetric chemical analysis.
- iv) Spectroscope.
- v) The firm should have Mechanical testing lab & Ultrasonic testing lab.
- vi) Microscopes for micro structural analysis.
- vii) Macro analysis facilities.
- viii) Firm should ensure the supply of items as per drawing dimension and technological requirements.
- ix) CMM to check the Cylinder Jacket after machining.
- x) Instruments / gauges to check the critical parameters of the component.