

MACHINED COMPONENTS (GROUP -VI)


| Sl no. | Nomenclature & drawing No. | Manufacturing technology & Testing / Inspection Facilities required to produce the item | | Must be possessed by the vendor in his premises (P&M list and testing / inspection equipment list to be submitted) | May be possessed by the vendor in his premises or out sourced (Self declaration to be submitted) | FIRM Compliance (Y/N) | Remarks |
|-----------------------|----------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|---------|
| 1 | Components as per enclosed list of Machined Components (Group VI) <i>Total items = 23 Nos</i> | TECHNOLOGY-1 | Milling & Drilling | HMC and/or VMC suitable to the components upto the size 250mm x 450mm x 250mm height with 0.010 accuracy | | | |
| | | TECHNOLOGY-2 | Raw material | | Firm should be capable to arrange the raw material defect free Aluminium Castings/ sheet metal as per drawing specification and standard. | | |
| | | TEST / INSPECTION-1 | 3D CMM | 3D CMM 500 x 500mm. | | | |
| | | | Surface Roughness Tester | Surface Roughness Tester for Ra & Rz values | | | |
| | | | Gauges | Standard Gauges for checking Holes and threads suitable to the requirement of the components. Firm should submit the undertaking in this regard that they will create the facilities within 6 months from the date of receipt of order. | | | |
| Measuring Instruments | Vernier Caliper, Groove Vernier, Radius gauge, Feeler Gauge etc. suitable to the requirement of the components | | | | | | |

Note : Justification for alternate facilities may be shared to prove that alternate facilities can be utilised to manufacture the item wherever the facilities are mentioned above are not available, but vendor has alternate facilities.


(D.SATHISH KUMAR)
WM/QA(NF& QMSC)


(J.P.SINGH)
GM-OPERATIONS I


(LUXMAN SINGH)
WM/TRG-II,HT & EP


Subham Bijlwan Subham
AH to (NEERAJ KUMAR)
QA-RIG(OE)


(K.DURAIRAJ)
JWM/Trans -II


(ANIMESH PAIK)
DGM/CA,TRG & RG

**RESTRICTED
(DRAFT/PROVISIONAL)
QUALITY ASSURANCE PLAN**

FOR

(HOUSING,UPPER,CASTING)

DRG.NO. 172.25.002-3/C

(LF NO: 3806208023)

No.HVF/T-72/QAP/25/HOUSING,UPPER,CASTING/242724-00

ISSUE No:00

DATE: NOV-2021

QUALITY ASSURANCE (RIG-SUB ASSEMBLY)

HEAVY VEHICLES FACTORY

AVADI CHENNAI – 600 054

QUALITY ASSURANCE PLAN (QAP)

FOR

HOUSING,UPPER,CASTING

172.25.002-3/C

PREPARED BY

REVIEWED BY



(V. RAJA)
JWM/QA (RIG-SA/ST&CT)



(C.NANDAKUMAR)
JWM/QA (RIG-SA)

APPROVED BY



(SUBHAM BIJLWAN)
AWM/QA-RIG-(SA)

ISSUED BY

QUALITY ASSURANCE (RIG- SUB ASSEMBLY)
HEAVY VEHICLES FACTORY
AVADI CHENNAI – 600 054

| Sl. no | CONTENTS | PAGE .No. |
|--------|-----------------------------------------|-----------|
| 1. | IMPORTANT NOTES | 4 |
| 2. | INTRODUCTION | 4 |
| 3. | AIM | 4 |
| 4. | SCOPE | 5 |
| 5. | DOCUMENTS | 5 |
| 6. | ITEM USED ON | 5 |
| 7. | LIST OF DRAWINGS | 6 |
| 8. | BILL OF MATERIAL | 6 |
| 9. | CONDITIONS OF USE/ STORAGE INSTRUCTIONS | 6 |
| 10. | SAMPLING PLAN | 6 |
| 11. | VISUAL INSPECTION | 7 |
| 12. | DIMENSIONAL CHECKS | 8 |
| 13. | MATERIAL CHECKS | 8 |
| 14. | ACCEPTANCE / PERFORMANCE TESTS | 9 |
| 15. | FITMENT AND PERFORMANCE TEST | 9 |
| 16. | INTERCHANGEABILITY | 10 |
| 17. | CALIBRATION CHECKS | 10 |
| 18. | MARKING/IDENTIFICATION | 11 |
| 19. | PRESERVATION CHECK | 11 |
| 20. | PACKING CHECK | 11 |
| 21. | DOCUMENTATION | 11 |
| 22. | REFERENCE | 12 |
| 23. | ANNEXURE - A | 13 |
| 24. | FIGURE OF THE SAMPLE | 14 |
| 25. | APPENDIX - A | 15 |

1. IMPORTANT NOTE

Note-1

This is only a provisional and will be amended from time to time according to the requirement. No addition, deletion and reproduction will be done without permission of The Sr. General Manager, Heavy Vehicles Factory, Avadi, Chennai – 54.

Note –2

Any instruction contained in this does not prejudice the terms and conditions of the contract what so ever. In case of any contradiction between the contents of this QAP and the clause in the contract, the latter will prevail.

Note-3

The stores should be manufactured strictly only as per the drawings supplied by the Inspection Authority and not as per the samples, if any received by the manufacturer for guidance purpose.

Note-4

Any amendment issued by the Inspection Authority shall be incorporated in the QAP and the records for the amendments carried out should be maintained as per the Performa at Appendix-"A".

Note-5

In case of any contradiction between the contents of this QAP and drawings issued along with the contract, the latter will prevail.

2. INTRODUCTION

1. This quality plan lays down the inspection and testing procedure to be carried out on the component **HOUSING,UPPER,CASTING TO DRG NO. 172.25.002-3/C** being procured indigenously. This is prepared, based on the acceptance standards and inspection parameters laid down in collaborators documents and on the inspection test standards followed in respect of similar indigenious items.

2. This QAP is the property of Government of India and is liable for amendments as and when required. The Sr. General Manager, Heavy Vehicles Factory, Avadi, Chennai – 600 054, is the inspecting Authority for this assembly. Any query / clarification on the content of this QAP shall be referred to this Factory. Any departure from these instructions is allowed only after written approval from the above authority. Notwithstanding the tests indicated in this QAP, the inspecting Officer has the right to carry out any test to check conformance to the paper particulars quoted in the Supply Order, which he may consider necessary to satisfy himself about the stores which he has to accept.

3. AIM

The QAP is aimed at standardizing the Inspection procedure and acceptance norm for **HOUSING,UPPER,CASTING TO DRG NO. 172.25.002-3/C**.

It also aims at giving adequate information to the manufacturer on the quality requirements so that the required quality control methods are established. This is also meant to guide authorized Inspection Officer in his

routine inspection and to set out main points to which his attention must be drawn to ensure that the accepted stores meet the stipulated standards.

4. SCOPE:

This QAP outlines in general terms, the checks and methods to be used during inspection of **HOUSING,UPPER,CASTING TO DRG NO. 172.25.002-3/C** including the technical requirements of the drawings. The recommended Quality Plan stipulated herein is mandatory and should be strictly adhered to. For inspection purpose, only the latest issue of this QAP will be made applicable and copies of this QAP can be obtained from the issuing authority i.e. The Sr. General Manager, Heavy Vehicles Factory, Avadi, and Chennai.

Note:

- i. Tender enquiry (TE) and supply order (S.O) will be issued with QAP stating that inspection will be done as per QAP.
- ii. In case of TE, It is responsibility of the vendor to obtain the copy of QAP and give the statement of compliance that vendor will abide by the QAP in case supply order is placed.
- iii. In case of S.O, it is the responsible of the vendor to obtained copy of QAP and give the statement of compliance that the vendor will follow QAP. However, GM/HVF reserves the right to revise/update the QAP from time to time.

5. DOCUMENTS:

- a) On placement of firm supply order, One set of relevant specification and technical instructions on the subject item can be obtained by the contractor from AHSP through DDO/HVF
- b) Any clarification required on these documents should be obtained from the Inspecting Authority i.e. The Sr. General Manager, Heavy Vehicles Factory, Avadi, Chennai – 600 054. Equivalents to the collaborators specifications and standards will be decided only by the Inspecting Authority and should not be unilaterally decided. For any change in the specifications, standards or written approval, any alterations in specification can be affected and not otherwise.
- c) The process instruction sheets supplied by the collaborators are available with the Authority Holding Sealed Particulars, i.e. The Controllerate of Quality Assurance (Heavy Vehicles), Avadi, Chennai for the reference. The relevant process sheets may be studied at the premises of the AHSP after obtaining necessary permission.
- d) The supplier after scrutiny of the concerned process sheets and connected paper particulars should establish the necessary production and inspection facilities. Particularly the inspection test rigs, stands, fixtures, template, gauges etc should be provided as recommended in these process sheets. If process sheet / Process Book is not available the details particulars/parameters available in the drawings to be strictly adhered.

6. ITEM USED ON:

1. 172.25.002-3 - CRANK CASE UPPER

7. LIST OF DRAWINGS:

Single (individual) item

| SI. NO. | DRG. NO | NOMENCLATURE | REMARKS |
|---------|----------------|-----------------------|---------|
| 1 | 172.25.002-3/C | HOUSING,UPPER,CASTING | - |

8. BILL OF MATERIALS:

Single (individual) items, details as below,

| SI. NO | DRG. NO | NOMENCLATURE | MATERIAL SPECIFICATIONS | Qty |
|--------|----------------|-----------------------|--------------------------------------|-----|
| 1 | 172.25.002-3/C | HOUSING,UPPER,CASTING | ALUMINIUM ALLOY AJ19 GOST 2685-75 | 1 |

Note: Vendor/Contractor may use approved alternate material if any specified in drawing/specification/GOST also Refer **Para No.13.

9. CONDITIONS OF USE/STORAGE INSTRUCTIONS

This assembly/item should be properly packed to protect from transit / handling damage and influence of atmospheric precipitations. In addition, the following parameters should be ensured:

- (a) The threaded parts if any should be covered with suitable plastic caps to prevent damages.
- (b) If the item consists of assemblies, each assembly should be packed separately.
- (c) The stores are to be suitably covered for preventing ingress of dust and Dirt/entry of sunlight / moisture.
- (d) The packaging slip shall contains
 - (i) Certificate of testing (NABL)
 - (ii) Guarantee/ Warranty Certificate
 - (iii) Service and maintenance instructions
 - (iv) Delivery Slip with Inspector's Acceptance Mark
 - (v) Undertaking letter / conformance of certificate.
- (e) The stores are not permitted to be stored together with oils. Petrol, acids, alkaline and other substances to avoid damage to the metal / rubber components.

10. SAMPLING PLAN:

| Sl. No. | Sampling Plan | Pilot * | Bulk |
|---------|------------------------|---------|----------------------------------------------------------------------------------------------------|
| (i) | Visual Inspection | 100% | 100% |
| (ii) | Dimensional Inspection | 100% | General Inspection level III, single sampling, Normal Inspection, AQL 2.5 of IS 2500 (Part-I)-2000 |
| (iii) | Material Inspection | 1 No | 1 No. for each batch of raw material or heat treatment lot as required by specifications. |

| | | | |
|--------|------------------------------------------------------------------------------|------------|-------|
| (iv) | Acceptance test | 100% | ----- |
| (v) | Pressure testing | ----- | ----- |
| (vi) | Machining / Fitment/ Performance trial on higher assembly / Tank | 02 Nos. | ----- |
| (vii) | Interchangeability Test | --- | ----- |
| (viii) | Test stand/Jigs/ Fixtures/Gauges/M andrels/etc. | 100 % | 100 % |
| (ix) | Marking/Identificati on | 100% | 100% |
| (x) | Packing/ Preservation | 100% | 100% |

Note:-

*This clause is applicable if mentioned in supply order or project sanction order.

A New (First time supplier of this item) supplier should obtain clearance from HVF for bulk production which will be issued only after inspection/evaluation of pilot samples by HVF.

During acceptance of castings, the following are to be checked as per Specification 172 TY6 & GOST 2685-75:

- chemical composition of steel;
- mechanical properties of steel;
- external view (absence of defects) and quality welding of casting defects;
- dimensions;
- hardness;
- absence of internal defects;
- macro/micro structure if any as per specification/GOST;
- wear & tear checks if any as per specification 172 TY6 & GOST 2685-75.

11. VISUAL INSPECTION [Sampling plan as per Para- 10 (i)]

The stores are to be visually examined on 100 % of pilot /bulk and same should be free from any defects and all the finishing requirements shall satisfy as indicated in technical conditions of the assembly / component drawing.

The components shall be checked for the following and should be free from the defects:

- Defects in construction
- Cracks/Flaws/blowholes/shrinkage/porosities
- Fitment of all components
- Presence of foreign particles
- Moisture and dust
- Corrosion of metal parts
- Mechanical imperfections & distortion

- Any form of deterioration of material and finishing.

Packing and preservation should be ensured as per drawings/relevant TY specification (To be ensured on receipt at consignee end).

12. DIMENSIONAL CHECK[Sampling plan as per Para- 10(ii)]

The dimensions of individual component, sub assembly and major assembly shall be checked and ensured as per respective drawing. Dimensional check should be carried out as per sampling plan. *However, the inspecting authority/rep. may at his discretion, tighten the inspection level and acceptance quality level on the critical items and adopt check point during manufacture.

12.1 HOUSING,UPPER,CASTING TO DRG.NO: 172.25.002-3/C

1. All dimensions shall be confirmed as per drawing/specification.
2. Surface finish / Roughness should be confirmed as per drawing and specification.
3. For admissible alternate method for manufacture in dimensions/material if any, refer drawing/specification

13) MATERIAL CHECKS [SAMPLING PLAN AS PARA – 10 (iii)]

Material specimen /test bars of the components shall be in conformity as per the material mentioned in the relevant documents/drawing. The material check will be carried out as per sampling plan. **However, if the manufacturer proposes any alternative material at the stage of tender enquiry, the same has to be approved and a written concurrence should be obtained from AHSP through DDO/HVF, before usage of such materials.

For each heat code/batch the test bars/test samples as specified in GOST/specification is to be submitted for testing chemical, mechanical, physical properties and other parameters of the casting and also the test certificates for the same tested by the supplier is to be submitted.

13.1 HOUSING,UPPER,CASTING TO 172.25.002-3/C

- a) The component should be manufactured from Aluminium alloy АЛ-9 GOST 2685-75.
- b) Chemical properties: As per Aluminium alloy АЛ-9 GOST 2685-75.

| Al | Si | Mg | Mn | Zn | Berilium | Tin | Cu | Pb |
|------|---------|---------|------|------|----------|------|------|------|
| | | | MAX | | | | | |
| Base | 6.0-8.0 | 0.2-0.4 | 0.50 | 0.30 | 0.10 | 0.01 | 0.20 | 0.05 |

The castings should be subjected to heat treatment. The mode of heat treatment for obtaining the given mechanical properties or the removal of internal stresses should be set by the manufacturing plant.

c). The mechanical properties of steel should comply with standards specified in table below

| GRADE OF ALLOY | TYPE OF HEAT TREATMENT | CASTING PROCESS | ULTIMATE TENSILE STRENGTH, MPa (kgf/mm ²) | RELATIVE ELONGATION IN % | HARDNESS IN BRINELL HB |
|----------------|------------------------|--------------------|-------------------------------------------------------|--------------------------|------------------------|
| | | | Not less than | | |
| АЛ-9 | T5 | Refer GOST 2685-75 | | | |

For details of other parameter/properties refer GOST 2685-75.

14) PERFORMANCES/ACCEPTANCE TEST: HOUSING,UPPER,CASTING to Drg. No.172.25.002-3/C.

The technical requirements shall be confirmed for acceptance of the component as specified in Specification and Drawing.

1. Drafts are not more than 1:30 towards the external side, unspecified radii of roundings are up to R5.
2. Component should meet the requirements of general part of 172TY6.
3. Heat treatment should be carried out as per mode T5 GOST 2685-75.
4. Casting dimensions unspecified by tolerances should be carried out with accuracy +2 mm.
5. Material should be marked on any unmachined surface by punching type П-0-5-Л08 GOST 2930-62.
6. Buckling of surface (see section A-A) should not exceed 1.5 mm.

Explanatory Note

1. Stage wise inspection and process of the component as specified in TD Book / Process Book / illustration book is to be confirmed by the supplier during manufacturing the components.
2. Firm shall submit the inspection process details/reports to HVF.
3. If required/applicable HVF shall witness/verify stage wise inspection/process details during manufacturing of the components.
4. The component may be subject to endurance test, when fitted in higher assembly as specified in process/ illustration/ TD book.

Note:

The Casting Manufacturers are required to follow the instructions strictly so far as supply of castings. (Refer specification 172 TY6 and GOST 2685-75)

15) FITMENT / MACHINING AND PERFORMANCE TEST:

- a. Pilot samples should be checked for fitment/machining trials and Performance test to ascertain the efficacy of the system under different operating conditions by fitting in higher assembly and repeating it for functional checks, wherever required.

- b. The item should possess appropriate material for machining as indicated in the drawing and should be supplied in such a way that the components to suit in machine/fixtures/Jigs etc to carry out machining.
- c. The component should be free from any defects after machining in trial and the casting should be in line with the parameters as specified in the GOST and Specification.
- d. The casting shall be clean, free from porosity blowholes, hard spots, Cold shut, distortion, cracks and other harmful defects as per the specification.
- e. The casting shall be well dressed and fettled and shall be readily machinable.
- f. Casting shall be cleaned/shot blasted and preservation coating is to be done after heat treatment as called for in the specification.
- g. No weld/repair should be carried out without prior permission from HVF.
- h. Testing methods for acceptance of the casting refer specification 172 TY6 and GOST 2685-75.

16) INTERCHANGEABILITY:

The assemblies should be interchangeable component wise and assembly wise, except the Component are to be supplied as a set and to be assembled selectively as per sampling plan.

17) CALIBRATION CHECKS

(TEST STANDS/JIGS/FIXTURES/GAUGES/INSTRUMENTS):

The supplier / Contractor should have suitable Instruments, Test Stand, jigs, fixture, mandrels, templates and gauges to carry out quality checks, to ensure conformance of components/assembly as per drawing and Specification /T.R points.

The supplier/contractor should submit calibration reports/certificates for instruments/fixtures/gauges/mandrels etc., which are used during process of inspection activities.

18) MARKING/IDENTIFICATION

Marking of the items is to be carried out as called for in the relevant drawing, drawing/T.R points.

Inscription if any on the components is to be carried out as called for in the drawing/T.R points. Unless otherwise specified in the drawing/ specification, marking should not be carried out over the components.

For traceability, marking of part No., Manufacturer name, supply order No, Serial No/Qty, batch No. and manufacture date & year are to be carried out. Suitable method can be adopted, provided that the above parameters are legible and considering the parameters mentioned in the drawing and specification.

19) PRESERVATION CHECK

- a) Preservative coatings are to be strictly adhered to as called for in the drawing. However, equivalent BIS Standards can also be followed, subject to the thickness of the coating/preservative is maintained as per the drawing/specification.

- b) Other preservations as necessary to prevent damages due to moisture and dust during process, storage and transit are to be carried out. Conventional Methods can also be resorted to.

20) PACKING CHECK

Components / Assemblies are to be packed separately to avoid damages during transit / handling of the same. Part No. and No. of sets are to be marked on the packing.

Packing and preservation should be ensured as per drawings/relevant TY specification (To be ensured on receipt at consignee end).

Finished products shall be wrapped / packed using black and opaque polyethylene sheet or bags.

21) DOCUMENTATION

- i. Firm has to maintain all the documents as per QAP with respect to the SI.No.to have traceability.
- ii. Vendor has to submit Bill of materials, Material test reports, Class 'C' /Endurance test reports (wherever specified in drawing/TY specification/QAP) and Complete PIR (pre-inspection report)at the time of offering the item for inspection. HVF will commence inspection only after scrutiny of these documents.
- iii. The testing/inspection responsibility to test all the parameters as per QAP and drawing specifications as mentioned in Annexure -A (enclosed).
- iv. Pre inspection reports (PIR) of firm like, 1. Chemical analysis, 2.Mechanical properties, 3. Pre-forming process, 4. Coating certification (wherever applicable), 5. Calibration reports of instruments and 6. 100% Dimensional inspection reports. 7. Pressure test (leakage test) if applicable, 8. Hardness checks, 9. Certificates for Macro/micro structure (wherever applicable), 10. Fracture test (if applicable) and other relevant test reports for acceptance of the Casting, etc.

22) REFERENCE:

- a) Drawing No: HOUSING,UPPER,CASTING TO 172.25.002-3/C
- b) Material specification as per drawing: ALUMINIUM ALLOY AL-9 GOST 2685-75.
- c) GOST 2685-75.
- d) Specification: 172 TY6.

| SL. NO. | CATEGORY | ASSEMBLY/SUB ASSEMBLY | TESTS/INSPECTION PARAMETERS | STANDARDS TO BE REFERRED | ACCEPTANCE CRITERIA | INSPECTION RESPONSIBILITY | | | REMARKS |
|---------|---------------------------------------------------|--------------------------------------|----------------------------------------------------------|--------------------------------------|-----------------------------------------------------------------|---------------------------|-----|------|------------------------------------------|
| | | | | | | Firm | HVF | DGQA | |
| 1 | HOUSING, UPPER, CASTING TO DRG. NO:172.25.002-3/C | Pre inspection reports (PIR) of firm | Firm has to produce all the document as per Para 21 (iv) | As per the relevant drawing and QAP. | Confirm to drawing and QAP as per bill of material | P | V | R | 100% by firm/vendor. |
| 2 | | Bill of material (BOM) | Firm has to prepare the BOM as per QAP | Refer QAP Para no: 8 or item list. | Confirm to QAP. | P | V | R | 100% by firm/vendor. |
| 3 | | Material tests | Chemical composition & Mechanical / Physical Properties | As per GOST 2685-75 | All the values to confirm with QAP (Para no:13.1 (a),(b) & (c) | P | W/V | R | SP followed by HVF. |
| 4 | | Dimensional checks | As per drawing & specification | As per Para 12.1 of QAP | All the values to confirm with QAP | P | W/P | R | 100% by firm/vendor, SP followed by HVF. |
| 5 | | Machining Trial | Suitability of component for machining | Refer QAP Para no.10 (vi) & Para 15 | Confirm to QAP Para no.10 (vi) & Para 15 | - | P | R | SP followed by HVF |
| 6 | | Hardness Checks | Hardness | As per Para 13.1 (C) | Confirm to QAP para 13.1 (C) | P | W/V | R | SP followed by HVF. |
| 7 | | Marking / traceability | Firm has to make marking / traceability records. | Refer QAP Para no: 18 | Confirm to QAP Para no:18 | P | V | R | 100% by firm/vendor, SP followed by HVF |
| 8 | | Preservation & packing | Firm has to make Preservation & packing records | Refer QAP Para no: 19 & 20 | Confirm to QAP Para no: 19 & 20 | P | V | R | 100% by firm/vendor. |

Note:

For conformity of the items (Chemical/Physical/Mechanical properties).

1. One sample per heat / batch shall be tested under NABL Lab/Govt. Approved lab by firm. In COVER of non-compliance to standards entire lot shall be rejected or not to use in production further.

2. For cross conformation of material, manufacturer has to submit sufficient quantity (as specified in GOST/Specification/supply order) test sample pieces for the items used / test slab and button for rubber items / HVF will draw samples from supplied lot for Witnessing (W) at HVF premises. In COVER of non-compliance to standards entire lot will be rejected.

P- Perform W- Witness V-Verify R-Review SP-Sampling Plan

FIG: HOUSING, UPPER, CASTING TO DRG. NO 172.25.002-3/C

