## QUALITY MONITORING INSTRUCTION FOR INSPECTION

Issue No : 01
Rev No:
Date of Issue

C 1005 (STRIP)		OFT/MI/30mm/C 1005
Rev.No	Amendment	Date
	-	

MATERIAL SPECIFICATION

30XPA, OST-3-98-80

ALT.MATERIAL

IS: 4367-91 DISIGNATION 25 Cr 13 Mo 6 'M' (or) IS: 5517-1993, DESIGNATION 25 Cr 13 Mo6 'M'.

(LRS-63mm)

CONDITION OF SUPPLY

: FULL FINISHED THROUGH FORGING ROUTE

**END USE** 

30mm CANNON.

## INSPECTION CHECK TO BE CARRIED OUT

Table 'A'

SL NO	CHARACTERISTICS	SPECIFICATION / REQUIREMENT	SAMPLE SIZE		
1.	Visual The component shall be free from cracks flacks, segregation porosities, slag inclusions, rolled in scale etc.,				
2.	Dimension	100% Dimension to check as per store drawing.			
3.	Chemical Composition (%)	STEEL 30XPA OCT 3-98-80:-  (As per Standard GOST 5160-70)  C = 0.28-0.33 Ni = 0.25-0.50  Si = 0.17-0.37 S = 0.025(Max)  Mn = 0.50-0.80 P = 0.025(Max)  Cr = 1.00-1.30 Cu = 0.20 (Max)  B = 0.001-0.0045  IS: 4367-91 DISIGNATION 25 Cr 13 Mo 6 'M'  C = 0.20 - 0.30 Cu = 0.25 (Max)  Si = 0.10 - 0.35 V = 0.05 (Max)  Mn = 0.40 - 0.70 Tin = 0.05 (Max)  Cr = 2.90 - 3.40 Boron = 0.0003 (Max)  Mo = 0.45 - 0.65 S = 0.02-0.035  Ni = 0.30 (Max) P = 0.035 (Max)  %Cu+10 (%Tin) = 0.50 (Max) S&P = 0.030 (Max)  IS: 5517-1993, DESIGNATION 25 Cr 13 Mo6 'M'  C = 0.20 - 0.30 Cu = 0.35 (Max)  Si = 0.10 - 0.35 V = 0.05 (Max)  Si = 0.10 - 0.35 V = 0.05 (Max)  Mn = 0.40 - 0.70 Tin = 0.05 (Max)  Mn = 0.40 - 0.70 Tin = 0.05 (Max)  Mn = 0.40 - 0.70 Tin = 0.05 (Max)  Mn = 0.40 - 0.70 Tin = 0.05 (Max)  Mn = 0.45 - 0.65 S = 0.035 (Max)  Ni = 0.25 (Max) P = 0.035 (Max)  Ni = 0.25 (Max)  P = 0.035 (Max)	One Sample Per Heat		

						C 1005
		STEEL 30XPA OCT-3-98-80				
4.			/mm² (Min)			
		Yield Strength = 130 Kgf	/mm² (Min)			
		Elongation = 9% (Mir				The department of the company
		Reduction of area = 40% (M	9.52			de l'Accessement
		Impact = 5 Kgfm/				
		IS: 4367-91 DISIGNATION 25 Cr 13 Mo 6 'M' (LRS 63mm)				
	Mechanical	Tensile Strength = 1550 MPa (Min)				One Sample
ч.	Properties	Yield Strength = 1300 MPa (Min)				
		Elongation = 8% (Min	1.00 m. 1.00 m.			Per Heat
	and the second s	Impact (Izod) = 15 Joule		~		
		IS: 5517-1993, DESIGNATION 25 Cr 13 Mo6 'M' (LRS 63mm)				
		Tensile Strength = 1500 MF	Pa (Min)	[rv2 02]	nm)	To a second of the second of t
		Yield Strength = 1300 MF				-
		Elongation = 8% (Min				***************************************
		Impact (Izod) = 14 Joules	,			
5,	Hardness	43.5 – 51.5 HRc. ( As per drawing)	5 (IVIIII)			
	Other Tests	(i) Macro Etch Test:		N	The state of the s	100%
6.		Acceptance Standard C-2, R-2,S-2 as per ASTM E-381-82 standard.				
		standard C-2, K-2,3-2	as per ASTM (	c-381-82	standard.	
		(ii) NMIR as per IS: 4163-1982.				
		With acceptance standard				
Ο.		A B				The second secon
		TI	C	*************************	)	
			Thin Thick	Thin	Thick	
		100-11	3 1	3	1	
		(Max) (Max) (Max) (Max) (I	Max) (Max)	(Max)	(Max)	
7	Protective Finish				100 %	
3.	Packing	the Packing of the Material shall be	done in such	a manna	tinent	100 %
	- sexting	The Packing of the Material shall be done in such a manner to avoid corrosion and damage in handling and transit.				
9.	Marking	Each Packing shall be legibly marked with				
	THE PART OF THE PA	, Qty, Heat No, OFT Supply order No etc.,				consignment

P.MURUGESAN HoS / QCM, CHECKED BY

U.MANGALASAMY HoS,'STD.CELL PREPARED BY

M.GIRISH KUMAR REDDY,

WM(QCM)

SUKESH GEHLAUT, Jt.GM (QCM) APPROVED

## Note:

- 1. The Raw material / component to be tested by the firm on selection of the sample by the firm itself for chemical composition and mechanical properties in NABL accredited approved Lab as per Table 'A'.
- 2. The Firm has to check for the dimensions, visual defects, packing and marking as per Table 'A'. After completion of tests as per Note-1 as above, the Firm has to submit the following documents to OFT.
  - The Raw material certificate from the original manufacturer, Heat number, and quantity purchased and number of bars is to be mentioned in the inspection letter to OFT.
  - II. The Chemical and Mechanical test certificates from NABL accredited approved lab as per Table 'A'.
  - III. Dimensional reports including visual as per Table 'A'.
  - IV. Guarantee / Warrantee certificate of supplier against the supply.
- 3. All the above Documents mentioned at Note No.2 above are to be forwarded to ED/OFT along with supply.
- 4. OFT shall verify all the documents as above and accord clearance to the firm for dispatch of the material to OFT if all documents are in order.
- 5. OFT/Trichy shall verify all the parameters as per Table 'A' and after satisfactory results, the material will be accepted /cleared accordingly.
- 6. Material has to be replaced 100% by the firm in case of non conformity to specification as per Table-A, during inspection at OFT, Trichy.

## **VERIFICATION OF INSPECTION DOCUMENTS**

SL_NO	INSPECTION DOCUMENTS		
1	The Raw material original Manufacturer's certificate, Details of Heat Number, Quantity purchased and number of Bars etc.,		
2	The Chemical and Mechanical test certificates from NABL accredited approved Lab.		
3	Dimension report including visual.		
4	Packing slip details.		

P.MURUGESAN HOSXOCM CHECKED

U.MANGALASAMY HoS/STD.CELL PREPARED

M.GIRISH KUMAR REDDY

SUKESH GEHLAUT Jt.GM(QCM) (APPROVED)