



QUALITY ASSURANCE PLAN (M2HB GUN IM PHASE)								Issue No : 01 Rev No: 00	
								Date of Issue / / 2021	
Drg . No.	5504065							QAP No: OFT/QAP/M2HB/5504065	
Nomenclature	EXTRACTOR ,OOW50BMG. REQD FOR EXTRACTOR ASSEMBLY SMALL ARMS CARTRIDGE (6008959)								
Material	STEEL, ASTM A331 OR A322: 4140,4340 FOR CASTING: STEEL, MIL-S-22141; IC 4140, IC 4340. TENSILE TEST SHALL NOT APPLY. INSPECTION SHALL BE IN ACCORDANCE WITH CLASS 1, GRADE A OF MIL-STD-2175.								
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by NAI or their authorised Rep. (Review/Witness) (*)	Remarks
Extractor (Raw material)	General appearance	Critical	Visual	100%	STEEL, ASTM A331 OR A322: 4140,4340 FOR CASTING: STEEL, MIL-S-22141; IC 4140, IC 4340. TENSILE TEST SHALL NOT APPLY. INSPECTION SHALL BE IN ACCORDANCE WITH CLASS 1, GRADE A OF MIL-STD-2175.		Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
	Chemical properties	Critical	Chemical Lab analysis	100%			Test report from NABL lab	R	
	Mechanical properties	Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
Heat Treatment	Mechanical properties	Critical	Mechanical Lab analysis	100%		HEAT AT 843°C - 871°C IN NEUTRAL ATMOSPHERE. OIL QUENCH. TEMPER ONE HOUR MINIMUM TO HARDNESS SPECIFIED RH C49-55.	Test report from NABL lab	R	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Protective Finish	General appearance	Critical	Visual and Dimensional Checks	100%	MIL-STD-171	Finish 5.3.1.2 (or) 5.3.2.2	Test report from NABL lab	R	
In process -As per Drawing 5504065	Dimensions Specified in the Inspection report of the component	Critical	Dimensional measurement	100%	As per Drawing 5504065		Firm Inspection report	R	
Final Inspection	General appearance	Critical	Visual and Dimensional Checks	100%	As per Drawing 5504065		Firm Inspection report	W	
<p>(*) Note : As per the MoU No: OFT / SRCG / M2HBGun / MoU /01 Dt: 20.09.2021, Clause no. 3(a), Sub clause (ii) & (iii) the following is applicable.</p> <p>(ii) For springs manufactured In-house (OFT) - Dimension inspection, Load Testing on sampling basis.</p> <p>(iii) For springs procured from vendors - from raw material to finished product QA by NAI, Trichy.</p>									


P. Narumugam
 Civilian Technical Officer (Mech)
 for Principal Inspector Of Naval Armament
 Tiruchirappalli.


 OFT **G. DEVENDIRAN, I.O.S.**
 ASSY WORKS MANAGER
 GOVT. OF INDIA, MIN. OF DEFENCE
 ORDNANCE FACTORY
 TIRUCHIRAPPALLI