



NOTES:-

- A. LOWER BOARDS (ITEM 2) WILL BE ATTACHED TO EACH WOODEN CUBE (ITEM 1) WITH 3 NAILS.
- B. UPPER BOARD (ITEM 4) WILL BE ATTACHED TO THE INTERMEDIARY BOARDS (ITEM 3) ONLY. AND WILL BE CONNECTED BY 2 NAILS THE BOTTOM END OF THESE NAILS WILL BE BENT BACK AND PRESSED INTO THE WOODEN BOARDS) THE UPPER BOARD WILL BE ATTACHED TO CUBES (THU. INTERMEDIARY BOARDS) WITH 3 THREAD NAILS.
- C. EQUAL DISTANCE MUST BE MAINTAINED BETWEEN EACH OF THE UPPER BOARDS.
- D. THE PALLET SHALL BE TREATED, CERTIFIED AND MARKED PROPER IPPC. PHYTOSANITARY MARKINGS & UN AND IMMO MARKING.
- E. ALL WOODEN CUBES MUST BE EQUAL IN HEIGHT AND THE PALLET MUST BE COMPLETELY LEVELED TO THE GROUND AND STEADY WHEN PLACE ON A STRAIGHT SURFACE.
- F. OVERALL LOAD CARRYING CAPACITY 2500KGS (MINIMUM)

ITEM NO	MATERIAL	NO. OFF	NOMENCLATURE	REMARKS
	PINE WOOD		आयुध निर्माणी, चांद	ORDNANCE FACTORY CHANDA
MASS:-				
PREP. BY	SIGN	DATE	PALLET II FOR PACKAGING	
OIC/R&D		06.02.24	RD 125 MM HE.	
DO/R&D			ASSLY. & STORE DRG. NO.	
OIC/U-VIII			DRG. NO. :- P/OP/S/K-850	
DO/U-VIII			D.TE. :- 06.02.24	
DO/U-VIII			SCALE :- 1:8	
DO/U-VIII			SHEET: 1 OF 1	
D.A. NO	DETAILS	INTL.		
DATE	REVISIONS			