

OFFICE NOTE



NO: QC Input/Wires/13

Dt.: 08-02-2021

Sub: Updating of Item Master for Manufacturing Technology & Testing Facility – Regarding.

Ref: PV/20-21/1. /Misc. PV Office Dt: 04-11-2020.

Data Requirement for Updating Item Master for Manufacturing Technology & Testing Facility which are enclosed herewith

Item		
Wire of Category KUPB7EX0.35-250 KUPB14EX0.35-250	Manufacturing Technology	<b>Essential Facility</b> 1. Stranding Machine 2. PE - Extruder 3. Copper Braiding Machine 4. Bunching Machine 5. Polyester Taping Machine 6. PVC - Extruder <b>Desirable Facility</b> 1. Wire Drawing Machine 2. Annealing Furnace/Pot 3. Tinning Facility
	Testing Facility	1. Micrometer 2. Vernier Caliper 3. Universal Testing Machine 4. Tinning per sulphate test 5. Hot & Cold Chamber as per requirement 6. Digital Multimeter 7. High Voltage Tester 8. Spark Tester
	Testing Lab Details	1. Lab accredited by NABL or not. 2. Assistance from or dependence on any central agency for testing/calibration etc.


Other Standard terms and conditions will be as under:


- 1) Desirable Manufacturing Facility if not available with firms. The firm has to enclose MOU letter of the reputed source for outsourcing facilities along with the technical bid offered.
- 2) Firm will arrange the required test facilities from NABL/Govt. Labs, if the same is not available with firm. The firm has to enclose MOU letter of the reputed source for outsourcing test facilities along with the technical bid offered.


Supporting documents to be submitted:


List of Testing/Inspection facilities available in-house and from outsourced firms to be submitted as per format:


S.No.	Name of the Testing/Inspection Equipment's	Make	Date of Calibration	Calibration agency (In-house/Out sources)

  
8/2/21  
KULWINDER SINGH  
JWM/QC

  
ANUPAM PAL  
JWM/PV

  
8/2/21  
ANUBHA AGGARWAL  
DGM/QC

  
8/2/21  
SK AGRAWAL  
Jt.GM/P

  
H.S. BHATIA  
AGM/QCO