QUALITY ASSURANCE PLAN									Issue No : 01 Rev No: 00	
									Date of Issue / / 2021	
org . No. 5564279										
Nommenclature	CAM, EXTRACTOR, COVER ,OOW50BMG. : REQD. FOR COVER SUB ASSEMBLY (5504081)								QAP No: OFT/QAP/M2HB/5564279	
Material	WROUGHT STEEL, ASTM A108: 1018-1022, ASTM A322,A331; 4118,8615 OR 8620. FOR CASTING: STEEL, MIL-S-22141, IC 8620. TENSILE TEST SHALL NOT APPLY. INSPECTION SHALL BE IN ACCORDANCE WITH CLASS 4 OF SAE AMS 2175.									
Component Nomenclature/ operations	Characteristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by NAI or their authorised Rep. (Review/Witness) (*)	Remarks	
Cam, Extractor, Cover (Raw material)	General appearance	Critical	Visual	100%	WROUGHT STEEL, ASTM A108: 1018-1022, ASTM A322,A331; 4118,8615 OR 8620. FOR CASTING: STEEL, MIL-S-22141, IC 8620. TENSILE TEST SHALL NOT APPLY. INSPECTION SHALL BE IN ACCORDANCE WITH CLASS 4 OF SAE AMS 2175.		Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency	
	Chemical properties	Critical	Chemical Lab analysis	100%			Test report from NABL lab	R		
	Mechanical properties	Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R		
Heat Treatment	Mechanical properties	Critical	Mechanical Lab analysis	100%	CARBURIZE FOR 3 TO 5 MINUTES AT 802°C - 816°C. OIL QUENCH. TEMPER ALL OVER AT 149°C FOR 1 HOUR MINIMUM TO FILE HARDNESS.		Test report from NABL lab	R		
Protective Finish	General appearance	Critical	Visual and Dimensional Checks	100%	AFTER ASSEMBLY		Test report from NABL lab	R	Firm will be undertaking 100 % Checks and	
In process -As per Drawing 5564279	Dimensions Specified in the Inspection report of the component	Critical	Dimensional measurement	100%	As p	As per Drawing 5564279 Firm Inspection R report		Pre inspection Report for the same be submitted		
Final Inspection	General appearance	Critical	Visual and Dimensional Checks	100%	As p	per Drawing 5564279	Firm Inspection report	W		

(*) Note: As per the MoU No: OFT / SRCG / M2HBGun / MoU /01 Dt: 20.09.2021, Clause no. 3(a), Sub clause (ii) & (iii) the following is applicable.

(ii) For springs manufactured In-house (OFT) - Dimension inspection, Load Testing on sampling basis.

(iii) For springs procured from vendors - from raw material to finished product QA by NAI, Trichy.

NAI ARREMANGLEDO Civilian Technical Officer (Mech) for Principal Inspector Of Navel Amesmont Tiruchirappalli. OFT COMPANY MANAGER
CONT. OF. IMPIA. MIN. OF. DEFENCE
ORDINAMER PACTOR
TOUCHIRASOPPINI