QUALITY ASSURANCE PLAN (SRCG IM PHASE)									Issue No : 01 Rev No: Date of Issue 05 /06/ 2021
Drg . No.	g . No. 066866A-00								
Nommenclature									OFT/QAP/SRCG/066866A
Material									
Component Nomenclature/ operations	Charateristics	Class	Type of check	Quantum of check	Reference document	Acceptance norms	Format of record	Inspection by QAE(N), Chennai or by Nominated Agency (Review/Witness)	Remarks
Spacer,Oil Reatainer (Raw material)	General appearance	Non Critical	Visual	100%	- Aluminium Alloy Plate 6061-T651 PER SAE AMS-QQ- A-250/11	Aluminium Alloy Plate 6061-T651 PER SAE AMS-QQ-A-250/11	Firm Inspection report	R	Sample will be drawn and sealed by Inspection Agency
	Chemical properties	Non Critical	Chemical Lab analysis	100%			Test report from NABL lab	R	
	Mechanical properties	Non Critical	Mechanical Lab analysis	100%			Test report from NABL lab	R	
In process - Turning,Drilling, Reaming	Dimensions Specified in the Inspection report of the component	Non Critical	Dimensional measurement	IS 2500 Level II AQL 2.5%	Approved Drg No. 066866A-00	As per Approved Drg No. 066866A-00	Firm Inspection report	W	Firm will be undertaking 100 % Checks and Pre inspection Report for the same be submitted
Chemical Conversion Coating	General appearance	Non Critical	Visual and Dimensional Checks	100%	MIL-DTL-5541F	Type II, Class 3.3	Firm Inspection report	R	
Final Inspection	General appearance	Non Critical	Visual and Dimensional Checks	IS 2500 Level II AQL 2.5%	Approved Drg No. 066866A-00	As per Approved Drg No. 066866A-00	Firm Inspection report	W	

^{*} Note: Process audit on Chemical Conversion coating and Traceability of Raw materials to Final Product (Man, Material, Machine and Methods)